



General Wall Assembly

Notes:

1. Shown is a general representation of a wall assembly with metal stud wall framing, HPCI barrier panel, furring channels and terra cotta tile exterior cladding.
2. The furring channels transfer the terra cotta tile cladding's gravity loads and wind loads through the HPCI panels into the wall framing studs. Reference detail HPCI-TC-02 for furring channel installation.
3. The terra cotta tile support tracks are shown with integral tile hooks. Support tracks with tile clips are similar. Reference the terra cotta manufacturer's information for specific tile support tracks.
4. It is the project designer's responsibility to confirm the suitability, structural adequacy and code compliance of the actual wall assembly and its components.

General Wall
Assembly

HPCI Barrier Panel
w/ Terra Cotta Cladding

HPCI-TC-01

Date: August 15, 2012